



**REBAR DETAIL**

| BARREL ABOVE F.L. | TOP OF INLET QUANTITIES |            | BARREL W/FLOOR QUANTITIES |            | C.I. STEPS |
|-------------------|-------------------------|------------|---------------------------|------------|------------|
|                   | LBS. STEEL              | C.Y. CONC. | LBS. STEEL                | C.Y. CONC. |            |
| 2'-0"             | 45.7                    | .25        | 86.68                     | .84        | 0          |
| 2'-6"             | 45.7                    | .25        | 97.12                     | 1.01       | 0          |
| 3'-0"             | 45.7                    | .25        | 117.37                    | 1.17       | 1          |
| 3'-6"             | 45.7                    | .25        | 127.71                    | 1.34       | 1          |
| 4'-0"             | 45.7                    | .25        | 148.06                    | 1.50       | 2          |
| 4'-6"             | 45.7                    | .25        | 158.40                    | 1.67       | 2          |
| 5'-0"             | 45.7                    | .25        | 178.74                    | 1.83       | 3          |
| 5'-6"             | 45.7                    | .25        | 189.09                    | 1.99       | 3          |

**CITY OF GRAND ISLAND**  
PUBLIC WORKS DEPARTMENT

DATE: JAN. 1976  
DRAWN BY L.D.C.  
APPVD. BY

**STANDARD TYPE "D" MODIFIED INLET**

**PLAN 126-A 30F4**